

ADDENDUM NO. 1

PROJECT: 30" WATERLINE RTE 607 AND W&OD AND ASHBY PONDS

NEIGHBORHOOD 2 – PHASE II

CONTRACT: 20090083 AND 20110016 IFB: 2011-032-220

To: Prospective Bidders of Record

Date: November 2, 2011

The following changes, additions, revisions, and/or deletions are hereby made a part of the Contract Documents for the aforementioned Project as fully and completely as if the same were fully set forth therein:

A. PART 3 – CONTRACT CONDITIONS

1. Supplementary Conditions, SC-5.04 – Contractor’s Liability Insurance, Item B.1. Change to read: The City of Fairfax and Dominion Virginia Power shall be listed as additional insured.
2. Supplementary Conditions, SC-5.04 – Contractor’s Liability Insurance, Item B.2. Change the amount of Excess Liability Insurance, combined single limit to \$2,000,000 each occurrence and \$2,000,000 annual aggregate.
3. Supplementary Conditions, NEW, SC-6.08 – Permits. Contractor is responsible for obtaining VDOT permit only as part of the Contract. All other required permits have been obtained by Owner. Contact VDT Residency at 703-737-2000 for permit costs.
4. General Conditions, NEW, SC-7.01 D – Related Work at Site. Contractor is advised that Loudoun County Parkway is scheduled to be widened to four lanes between the W&OD Trail and Gloucester Parkway in 2012. Contractor shall coordinate its Work with the work of the contractor(s) performing this widening of Loudoun County Parkway.

B. PART 5 – DRAWINGS

1. Add a General Note, “Any required shutdown of existing water to be coordinated with and performed by Loudoun Water,” to all drawings included with IFB 2011-032-220.
2. Changes to sheet 14 of drawings titled, 30” Waterline Rte 607 and W&OD, Project 20090083.
 - a. Add Dominion Virginia Power Blasting Requirements as follows:



ADDENDUM NO. 1
IFB 2011-032-220
NOVEMBER 2, 2011
PAGE 2 OF 2

No Blasting will be allowed within 100 feet of Dominion Virginia Power facilities until Contractor submits and receives approval of a blasting plan from Dominion Virginia Power's structural engineer. See attached Exhibit "E" for Dominion Virginia Power blasting conditions and blasting plan example.

3. Changes to drawings titled, Ashby Ponds Neighborhood 2 – Phase II, Project 20110016, sheet 74 of 121. (Project consists of 16 total sheets, including cover.)
 - a. Remove the 12" valve from station 0+00 for Watermain G2.
 - b. Restrained joint pipe to be used for Watermain G2 from stations 0+00 to 0+30, inclusive. FlexRing®, TRFlex, and Snap-Lok™ are acceptable types of restraint.
 - c. 12"x12" inverted tees at stations 0+00 and 0+30 on Watermain G2 shall be by cut in tees.
4. Add a note to sheet 16 of the drawings titled, 30" Waterline Rte 607 and W&OD, Project 20090083, that a runner shall be welded in the existing 48" casing that crosses under Pacific Boulevard in accordance with Standard Detail, G-12, Casing Installation. The purpose of the runner is to keep the carrier pipe from spinning during installation. The diameter of the casings is large enough to allow for installation of this runner.

END OF ADDENDUM

