

**LOUDOUN COUNTY SANITATION AUTHORITY
(DBA LOUDOUN WATER)**

44865 Loudoun Water Way
Ashburn, Virginia 20147
Telephone: 571-291-7700

24" WATERLINE RELOCATED ROUTE 621 TO TALL CEDARS PARKWAY RED DOT 24
PROJECT ID NO. 20100015

NOTICE OF ADDENDUM

ADDENDUM NO. 2
FEBRUARY 24, 2011

Bidders on the above-named Project are hereby notified the documents have been revised as indicated below. All bid submittals shall conform to this Addendum. Bidders are responsible for familiarizing themselves with these modifications and the effect they may have on the scope of work.

CONTRACT DOCUMENTS AND PROJECT DRAWINGS

1. Contract Documents and Project Drawings – clarifications on cathodic protection
 - Install 20# anodes every 10' between stations 23+84 and 24+34, 33+00 and 34+00, 42+84.75 and 43+34.75, 54+55 and 55+05, and 60+12 and 60+62.
 - All joints must be bonded between the stations 23+84 and 43+34.75 and stations 54+55 and 60+62.
 - Loudoun Water will perform all aspects of the close-interval survey per Section 13000-7 F.1.
2. Contractor to provide temporary fencing in the vicinity of stations 28+00 to 45+00 to keep livestock out of the construction area and to allow the livestock to remain on the property.
3. Root pruning requirements are specified on sheet 15 of the Project Drawings under Tree Protection. Contractor to use judgment and hire Arborist for final determination on any additional work requirements related to tree protection.
4. Contract Document, page 02315-4, paragraph 3.02 D2 & D3
 - No requests to date to cut and stack the wood as suggested under D2. Contractor will be advised by Loudoun Water of any such request.
5. Contractor to provide stakeout prior to construction.

6. Loudoun Water performs asbuilt survey.
7. Spreading of spoils to be consistent with the Loudoun Water Engineering Design Manual, Chapter 4 Installation Requirements, with the exception of adhering to the notes and details offered on Sheet 15 of the Project Drawings.

END OF ADDENDUM NO. 2